


# **BRUHAT BANGALORE MAHANAGARA PALIKE**



**Asst.Executive Engineer,  
Shettyhalli Sub Division,**

**Name of Work** Construction of Culverts at AYR Layout, in Ward  
No.12, in Shettyhalli Sub Division

**Est Cost:6.00 (Rs in Lakhs)**

# Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Construction of Culverts at AYR Layout, in ward no.12, in Shettyhalli Sub-Division

Est .Cost Rs. 6.00 Lakhs

| SI No | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit     | No  | L    | B             | D    | Qty   | Rate    | Amount   |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----|------|---------------|------|-------|---------|----------|
| 1     | KSRRB 300-1: Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications. in Hard Soil. MORTH/ Chapter 3. Page No. 141/ Item No. 19.2/ PWD SR                                                                                                                                         | Cum      |     |      |               |      |       |         |          |
|       | Culverts                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          | 3   | 5.00 | 2.00          | 1.20 | 36.00 |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          | 2   | 5.80 | 2.00          | 1.20 | 27.84 |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          | 2   | 6.50 | 2.00          | 1.20 | 31.20 |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |     |      |               |      | 95.04 | 115.56  | 10983.00 |
|       | Basic Rate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 107.00   |     |      |               |      |       |         |          |
|       | Area Weightage 8%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 8.56     |     |      |               |      |       |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 115.56   |     |      |               |      |       |         |          |
| 2     | KSRB 4-1.4: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.86cum and fine aggregate @ 0.58cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2, Page No. 12/ Item No. 4.3/ PWD SR 2015-16.                | Cum      |     |      |               |      |       |         |          |
|       | For Culverts                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          | 3   | 5.00 | 2.00          | 0.15 | 4.50  |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          | 2   | 5.80 | 2.00          | 0.15 | 3.48  |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          | 2   | 6.50 | 2.00          | 0.15 | 3.90  |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |     |      |               |      | 11.88 | 5070.60 | 60239.00 |
|       | Basic Rate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 4,695.00 |     |      |               |      |       |         |          |
|       | Area Weightage 8%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 375.60   |     |      |               |      |       |         |          |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 5,070.60 |     |      |               |      |       |         |          |
| 3     | KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregate @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2, Page No. 12/ Item No. 4.1/ PWD SR 2015-16 | Cum      |     |      |               |      |       |         |          |
|       | For Side Walls                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          | 2x3 | 5.00 | (0.75+0.45)/2 | 0.90 | 16.20 |         |          |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          |      |               |      |       |          |                   |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|------|---------------|------|-------|----------|-------------------|
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 2x2                                      | 5.80 | (0.75+0.45)/2 | 0.90 | 12.53 |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 2x2                                      | 6.50 | (0.75+0.45)/2 | 0.90 | 14.04 |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          |      |               |      | 42.77 | 5404.32  | 231132.00         |
|   | Basic Rate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 5,004.00                                 |      |               |      |       |          |                   |
|   | Area Weightage 8%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 400.32                                   |      |               |      |       |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 5,404.32                                 |      |               |      |       |          |                   |
| 4 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16. | Cum                                      |      |               |      |       |          |                   |
|   | For RCC Covering 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                          | 3    | 5.00          | 1.80 | 0.23  | 6.21     | Qty1              |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          | 2    | 5.80          | 1.80 | 0.23  | 4.80     | Qty1              |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          | 2    | 6.50          | 1.80 | 0.23  | 5.38     | Qty1              |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          |      |               |      |       | 16.39    | 6332.04 103810.00 |
|   | Basic Rate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 5,863.00                                 |      |               |      |       |          |                   |
|   | Area Weightage 8%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 469.04                                   |      |               |      |       |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 6,332.04                                 |      |               |      |       |          |                   |
| 5 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe 415 Page No. 19/ Item No. 4.46.1/ PWD SR 2015-16                      | Tonne                                    |      |               |      |       |          |                   |
|   | For Side Walls 5kgs/Sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 3x2x2x5.0x0.90=54.00x5kg = 270.00kgs/Sqm |      |               |      | 2.70  |          |                   |
|   | For Side Walls 5kgs/Sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 2x2x2x5.8x0.90=41.76x5kg = 208.80kgs/Sqm |      |               |      | 2.08  |          |                   |
|   | For Side Walls 5kgs/Sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 2x2x2x6.5x0.90=46.08x5kg = 234.00kgs/Sqm |      |               |      | 2.34  |          |                   |
|   | For RCC Covering Qty1 80kg/cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                          |      |               |      | 13.12 |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                          |      |               |      | 20.24 |          |                   |
|   | Basic Rate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 64,635.00                                |      |               | Say  | 2.02  | 69805.80 | 141008.00         |
|   | Area Weightage 8%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 5,170.80                                 |      |               |      |       |          |                   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 69,805.80                                |      |               |      |       |          |                   |

[illegible]



## CERTIFICATE

- 1 The Work spot has been inspected and the work found to be necessary
- 2 The Estimate is prepared as per the PWD SR 2015-16
- 3 The Provision made in estimate are adequate and essential
- 4 This area comes under BBMP limits.

Pavani N.K.  
Asst Engineer  
Ward No-12

  
Asst Executive Engineer  
Shettyhalli Sub-Division  
BBMP

  
Executive Engineer  
Dasarahalli Zone  
BBMP





Pani-N.K.

Shankar




ಪ್ರಕಾಶ್ ಕಾರ್ತಿಕೇಶನ್ ಅಧಿಕಾರಿಗಳು  
ಶಿಬಿರಕ್ಕೆ ಕಾಲಿಟ್ಟು, ಕಾರ್ತಿಕೇಶನ್ ಮಂಡಳಿ,  
ಬಹಳ ದಿನಗಳಿಂದ ಮಹಾನಗರ ಪಾಲಿಕೆ



Ravi N.K.

Jhail

Sub-Division



CULVERT EX

Paez N. C.

6/11/20

ವಹಾರಾದ ಕಾಂತ್ಲೆವಾಣಿಗನೇ ಇಲ್ಲಾಯಂಕರವರು  
ಶಿಕ್ಷಕರೈ ಉಪವಿಜ್ಞಾನಿ ಕಾಂತ್ಲೆವಾಣಿಗನೈ ವಲಯ,  
ಬಿಪತ್ ಚಿಂಗಿಕರು ಮಹಾರಗನರ ಕಾಲಿಲ್ಲಿ